STREETS, SIDEWALKS, PUBLIC PARKS, BUILDINGS, GROUNDS, AND GENERAL IMPROVEMENT COMMITTEE
Moseley
Blank
Liming

ORDINANCE NO. 58-2026

AN ORDINANCE ACCEPTING THE BID OF SHELLY & SANDS, INC. FOR THE HELMICK DRIVE, CHESTER AVENUE, AND WESTVIEW AVENUE RESURFACING PROJECT AND DECLARING AN EMERGENCY.

NOW, THEREFORE, BE IT ORDAINED BY THE COUNCIL OF THE VILLAGE OF LORDSTOWN, COUNTY OF TRUMBULL, STATE OF OHIO:

Section I: That the Streets, Sidewalks, Public Parks, Buildings, Grounds and General Improvements Committee recommends that Village Council authorize the Village to accept the bid of Shelly & Sands, Inc. for the Helmick Drive, Chester Avenue, and Westview Avenue Resurfacing project for the Village of Lordstown, as being the lowest and best bid.

Section II: That the Council of the Village of Lordstown concurs with the recommendation from the Streets, Sidewalks, Public Parks, Buildings, Grounds and General Improvements Committee and hereby authorizes the Village to accept the bid of Shelly & Sands, Inc. (a copy of which is attached hereto as **Exhibit "A"**, the terms of which are incorporated by reference and made a part of this Ordinance) for the Helmick Drive, Chester Avenue, and Westview Avenue Resurfacing project for the Village of Lordstown at a cost not to exceed One Hundred Twenty-Nine Thousand One Hundred Twenty-One and 66/100 Dollars ($129,121.66), as being the lowest and best bid and the same is hereby accepted.

Section III: That payment for said services shall not exceed One Hundred Twenty-Nine Thousand One Hundred Twenty-One and 66/100 Dollars ($129,121.66) and shall be paid from the 303.330.55000 Streets Capital Improvement Fund.

Section IV: That this Ordinance is hereby declared to be an emergency measure necessary for the public health, safety and welfare and for the further reason that the contract must be accepted, awarded, and completed by October 31, 2026.

Section V: That the passage of this Ordinance and all deliberations relating to the passage of this Ordinance were held in open meetings in accordance with the provisions of Ohio Revised Code Section 121.22.

Passed in Council this 5 day of October, 2026.

_____, Mayor

_____, Clerk

PROPOSAL

ADDRESS:

Proposal must be sealed and addressed to:

Lordstown Village Clerk

1455 Salt Springs Road SW

Warren, Ohio 44481

AND ENVELOPE MARKED

LORDSTOWN VILLAGE – 2026 Hot Mix Resurfacing Project

AND WITH THE NAME AND ADDRESS OF THE BIDDER:

LOCATION/TIME:

Bids to be opened at (Public entity to specify):
September 16, 2026 at 2:00 P.M.

In submitting this proposal, it is understood that the right is reserved by the Board of Village Council to reject any or all bids.

It is also agreed that this proposal may not be withdrawn for a period of sixty (60) days from the opening thereof in which time a written contract will be entered into with the Village of Lordstown.

NAME (BIDDER): Shelly & Sands, Inc.

ADDRESS (BIDDER): 1450 N. Bailey Road
North Jackson OH
44451

BID SHEET
2026 Hot Mix Resurfacing Project
VILLAGE of LORDSTOWN

Hemlick Dr. (from Salt Springs Rd to dead end), Chester Ave. (from dead end to dead end) and Westview Dr. (from Chester Ave. To dead end.)

Existing Pavement Area

Hemlick Dr.	645 L.F. @ 20' Avg. Width / 9	= 1434 S.Y.
	intersection @ Salt Springs.	= 75 S.Y.
		1,509 S.Y.
Chester Ave.	1374 L.F. @ 19.5' Avg. Width / 9	= 2,977 S.Y.
	intersection @ Helmick Dr.	= 204 S.Y.
		3181 S.Y.
Westview Dr.	210 L.F. @ 18 Avg. Width / 9	= 420 S.Y.
	intersection @ Chester Ave.	= 15 S.Y.
		435 S.Y.
	Total	5,125 S.Y.

MATERIAL CALCULATIONS

202 WEARING COURSE REMOVED
Butt Joint @ Hemlick Dr. and Salt Springs, and as directed
55 L.F. x 4' width/9 = 24.44 S.Y. — Use 24 S.Y.

251 PARTIAL DEPTH PAVEMENT REPAIR, 3" — Use 413 S.Y.

441 ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, (448)
5,125 S.Y. x 0.5" depth / 36 + 5% = 74.74 C.Y. — Use 75 C.Y.

441 ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG 64-22, AS PER PLAN
5,125 S.Y. x 1.25" depth / 36 + 5% = 168.84 C.Y. — Use 187 C.Y.

407 NON-TRACKING TACK COAT
5,125 S.Y. x 0.12 Gal./S.Y. = 615 Gal. — Use 615 Gal.

441 ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), (DRIVEWAYS)
Use 5 C.Y.

301 ASPHALT CONCRETE BASE, PG 64-22, 6" — Use 4 C.Y.

659 SEEDING AND MULCHING — Use 990 S.Y.

617 COMPACTED AGGREGATE — Use 105 S.Y.

614 MAINTAINING TRAFFIC — Use Lump Sum

623 CONSTRUCTION LAYOUT STAKES AND SURVEYING — Use Lump Sum

624 MOBILIZATION — Use Lump Sum

ITEM	APPROXIMATE UNIT QUANTITIES	DESCRIPTION	UNIT PRICE BID	TOTAL AMOUNT BID
202	24 S.Y.	Wearing Course Removed	$ 80.00	$ 1920.00
251	413 S.Y.	Partial Depth Pavement Repair, 3"	$ 65.00	$ 26845.00
441	75 C.Y.	Asphalt Concrete Intermediate Course, Type 1, (448)	$ 300.50	$ 22537.50
441	187 C.Y.	Asphalt Concrete Surface Course, Type 1, (448), PG 64-22, As Per Plan	$ 241.25	$ 45113.75
407	615 Gal.	Non-Tracking Tack Coat	$ 3.05	$ 1875.75
441	5 C.Y.	Asphalt Concrete Surface Course, Type 1, (448), (Driveways)	$ 1650.00	$ 8250.00
301	4 C.Y.	Asphalt Concrete Base, PG64-22, 6"	$ 118.00	$ 472.00
659	990 S.Y.	Seeding and Mulching	$ .40	$ 396.00
617	105 C.Y.	Compacted Aggregate	$ 103.00	$ 10815.00
614	Lump Sum	Maintaining Traffic	$ 5396.66	$ 5396.66
623	Lump Sum	Construction Layout Stakes And Surveying	$ 500.00	$ 500.00
624	Lump Sum	Mobilization	$ 5000.00	$ 5000.00
		GRAND TOTAL =		$ 129,121.66